



*The Good Life*

REVISIONS

NO	DATE	DESCRIPTION
??		??

NOTES

1. INSTALL CONNECTOR LINE FROM EXISTING BLOW-OFF ASSEMBLY TO NEW MAIN FOR FILLING, TESTING, AND STERILIZING NEW MAIN.
2. CONNECTOR LINE TO BE ASSEMBLED WITH CHECK VALVE AND TO BE OPERATED INDEPENDENT OF EXISTING MAIN.
3. CONTRACTOR IS NOT TO DISTURB BLOCKING ON EXISTING LINE.
4. FINAL CONNECTION TO EXISTING MAIN TO BE MADE ONLY AFTER TOTAL PROJECT IS ACCEPTED BY THE CITY OF TEGA CAY.
5. VALVES ON THE EXISING SYSTEM ARE TO BE OPERATED ONLY BY CITY PERSONNEL.
6. ONLY ONE CONNECTION WILL BE ALLOWED BETWEEN THE EXISTING SYSTEM AND THE NEW CONSTRUCTION UNTIL ALL TESTING AND DISINFECTION ARE COMPLETE.

CITY OF TEGA CAY  
LAND DEVELOPMENT  
STANDARDS

# JUMPER CONNECTION

STD. NO	REV
?-?	?